Tender/Proposal Detail

Tender/Proposal

142394

Invitation T-1/BWDB/Kishore/6575,

Reference No. : Date: 28/11/2017

Closing Date and

Time:

ID:

19-Dec-2017 12:30 Opening Date and

Time:

19-Dec-2017 12:30

Procuring Entity: Kishoreganj WD Division

BWDB/Kish/HFMLIP/PW-19

Re-excavation of Berachapra River KM0.00 to KM15.82015.820KM and Atoplal River KM0.00 to KM7.1137.113KM Total22.933 by Dredger of Naogaon Haor Sub-Project in c/w Haor Flood Management and Livelihood Improvement ProjectBWDB Part under Kishoregonj WD Division BWDB Kishoregonj during the FY2017-18 and

FY2018-19.

Special Instructions:

01. Tenderers should visit the working site before submission of tender.

02. RDPP is in approval process, Notification of Award (NOA) will be issued after approval of RDPP.

03. No claim what so ever will be entertained if NOA is not issued.

04. The work of the packages may be totally dropped, decrease or increase as per field condition/design/budget allocation for which no claim shall be entertained.

field condition/design/budget allocation for which no claim shall be entertained. 05. According to PPA 2006 Act 7(3) (Amendment) The Tenders having quoted the offer in percentage is more than 10%(ten percent) above or less than 10%(ten

percent) less of the official estimated cost will be rejected.

06. In case of credit line certificate, it should be in Letter of Commitment for Bank's under taking for Line of Credit(Form PW3-7) that attached in section -8. No alteration is allowed, in failing, tender may not be accepted. In case of Bank Statement, the amount of minimum balance shall remain constant of Tk. 200.00 Lakhs during the evaluation period. During verification, required amount of Liquid Asset if not found available in Tenderer mentioned account, then the submitted bank statement will not be considered in the evaluation. For the winner bidder, this amount shall have to be used as a working capital for this package. In this regards,

Tenderer has to be submitted a commitmen letter.

Package No	Package Description
19	Re-excavation of Berachapra River KM0.00 to KM15.82015.820KM and Atoplal River KM0.00 to KM7.1137.113KM Total22.933 by Dredger of Naogaon Haor Sub-Project in c/w Haor Flood Management and Livelihood Improvement ProjectBWDB Part under Kishoregange WD Division BWDB Kishoregonj during the FY2017-18 and FY2018-19.

Dolly Construction Ltd-SA-SI (JV) (JVCA)

Bill of Quantities

Bill of	Quantities	;							
Item no.	Group	Item Code (if any)	Description of Item	Measurement Unit	Quantity	Unit Price In figures (BDT)	Unit Price In Words (BDT)	Total Price In Figures (BDT)	Total Price In Words (BDT)
			Preparation and mobilization of the Site for Construction of Submersible Embankment or other Structural Components in c/w "Haor Flood Management and Livelihood Improved						

1	Approved rate	Approved rate	Improvement Project(BWDB Part) as per Technical Specifications, including land lease, rental charges, obtaining permissions for work, developing work area, preparation of platform for temporary semi pucca site office(40sqm), CI Sheet labour sheds(200sqm), CI Sheet Stores(200sqm), supply of wooden & cane seated furniture etc. as specified and as per Contractor's Method Statement and as per direction of Engineer in charge.	LS	1.000	220000.001	Two Lakh Twenty Thousand point Zero Zero One	220000.001	Two Lakh Twenty Thousand point Zero Zero One
2	Approved rate	Approved rate	Provide and maintain 1 (one) no. Engine boat with boatmen having sun and rainproof cover to facilitate supervision by the Engineer/Engineer's Representative during whole construction period of the work as per Technical Specification, Contractor's Method Statement and as per direction of Engineer in charge.	Days	60.000	6800.001	Six Thousand Eight Hundred point Zero Zero One	408000.060	Four Lakh Eight Thousand point Zero Six
3	Approved rate	Approved rate	Demobilization and clean-up of the site upon completion of the works, as per Specifications and Contractor's Method Statement and as per direction of Engineer in Charge	LS	1.000	120000.001	One Lakh Twenty Thousand point Zero Zero One	120000.001	One Lakh Twenty Thousand point Zero Zero One
4	Approved rate	Approved rate	Providing and maintaining adequate portable water supply by installing 6 Nos. of tube well and sanitation facilities by installing 6 Nos. of sanitary latrines for usage of labours, officials and	LS	1.000	250000.001	Two Lakh Fifty Thousand point	250000.001	Two Lakh Fifty Thousand point

			others for prevailing the hygenic and healthy environment at allover the working site As per direction of the Engineer in charge.				Zero One		Zero One
5	Approved rate	Approved rate	Mobilize, strengthen required land based construction equipment such as excavator, dump truck, chain dozer, vibro-compactor, and plants such as generator for site electrification, digital camera for taking photographs and digital video camera for recording/Taking photograph all sequences of works etc for keeping records of the Works by providing following information including transfer to site, complete for the purposes stated in the Technical Specification and Contractor's Method Statement and as per direction of Engineer in charge.	LS	1.000	250000.001	Two Lakh Fifty Thousand point Zero Zero One	250000.001	Two Lakh Fifty Thousand point Zero Zero One
6	Approved rate	Approved rate	Operate , maintain of plant and equipment such as generator for site electrification, for the purpose stated in the Technical Specification and in the Contractor's Method Statement and as per direction of Engineer in charge.	LS	1.000	150000.001	One Lakh Fifty Thousand point Zero Zero One	150000.001	One Lakh Fifty Thousand point Zero Zero One
7	04-150	04-150	Manufacturing and supplying R.C.C. (1:2:4) BM Pillars of size 15cmx 15cmx75cm, with 40cmx40cmx10cm base having 3 nos.10mm dia MS.bar each way at base,4nos.10mm dia vertical bar and 8nos 6mm dia ring,excluding cost of M.S.works for reinforcement but including cost of form works,	nos	24.000	644.901	Six Hundred and Forty- Four point Nine	15477.624	Fifteen Thousand Four Hundred and Seventy- Seven

			concreting, plastering at top, finishing surface, curing etc. complete, with inscription of "BWDB", on exposed surface etc. complete as per direction of Engineer in charge.				Zero One		μυπι σιχ Two Four
8	04-160	04-160	Fixing in position B.M. pillars and kilometer posts of size 15cmx15cmx75cm with 40cmx40cmx10cm base, embedding 45cm below G.L. including carriage, earth cutting, backfilling, ramming, etc. complete as per direction of Engineer in charge.	nos	24.000	48.937	Forty- Eight point Nine Three Seven	1174.488	One Thousand One Hundred and Seventy- Four point Four Eight
9	16-100	16-100	Erection of bamboo profile with full bamboo posts and pegs not less than 60mm in diameter and coir strings etc. complete as per direction of Engineer in charge.	nos	461.000	292.291	Two Hundred and Ninety- Two point Two Nine One	134746.151	One Lakh Thirty- Four Thousand Seven Hundred and Forty-Six point One Five One
10	Approved rate	Approved rate	River dredging work as per approved design and specification including mobilizing (and subsequent demobilizing) necessary dreders, ancillary equipments, floating pipes, shore pipes and other necessary suppliies, disposal of dredged material shall not be done within river and it shall be disposed to safe distance which specified in the drawing by installing necessary floating and shore pipes with all other ancillary work complete as per requirement and direction of Engineer in charge.	cum	577753.680	146.501	One Hundred and Forty-Six point Five Zero One	84641491.874	Eight Crore Forty-Six Lakh Forty- One Thousand Four Hundred and Ninety- One point Eight Seven Four

							Grand Total:	86190890.202	Crore Sixty- One Lakh Ninety Thousand Eight Hundred and Ninety point Two Zero Two
--	--	--	--	--	--	--	-----------------	--------------	---

This Bill of Quantities is Electronically Signed by Mr. Mohammed on behalf of Dolly Construction Ltd-SA-SI (JV)

LT-MC JV (JVCA)

Bill of Quantities

Bill of Quantities											
tem no.	Group	Item Code (if any)	Description of Item	Measurement Unit	Quantity	Unit Price In figures (BDT)	Unit Price In Words (BDT)	Total Price In Figures (BDT)	Total Price In Word (BDT)		
1	Approved rate	Approved rate	Preparation and mobilization of the Site for Construction of Submersible Embankment or other Structural Components in c/w "Haor Flood Management and Livelihood Improved Improvement Project(BWDB Part) as per Technical Specifications, including land lease, rental charges, obtaining permissions for work, developing work area, preparation of platform for temporary semi pucca site office(40sqm), CI Sheet labour sheds(200sqm), CI Sheet Stores(200sqm), supply of wooden & cane seated furniture etc. as specified and as per Contractor's Method Statement and as per direction of Engineer in charge.	LS	1.000	967050.851	Nine Lakh Sixty- Seven Thousand AND Fifty point Eight Five One	967050.851	Nir Lak Sixty Seve Thousar AN Fiff poi Eigl Five Or		

			Provide and						
2	Approved rate	Approved rate	maintain 1 (one) no. Engine boat with boatmen having sun and rainproof cover to facilitate supervision by the Engineer/Engineer's Representative during whole construction period of the work as per Technical Specification, Contractor's Method Statement and as per direction of Engineer in charge.	Days	60.000	5000.001	Five Thousand point Zero Zero One	300000.060	Three Lakh point Zero Six
3	Approved rate	Approved rate	Demobilization and clean-up of the site upon completion of the works, as per Specifications and Contractor's Method Statement and as per direction of Engineer in Charge	LS	1.000	112344.101	One Lakh Twelve Thousand Three Hundred and Forty- Four point One Zero One	112344.101	One Lakh Twelve Thousand Three Hundred and Forty- Four point One Zero One
4	Approved rate	Approved rate	Providing and maintaining adequate portable water supply by installing 6 Nos. of tube well and sanitation facilities by installing 6 Nos. of sanitary latrines for usage of labours, officials and others for prevailing the hygenic and healthy environment at allover the working site As per direction of the Engineer in charge.	LS	1.000	111148.951	One Lakh Eleven Thousand One Hundred and Forty- Eight point Nine Five One	111148.951	One Lakh Eleven Thousand One Hundred and Forty- Eight point Nine Five One
5	Approved rate	Approved rate	Mobilize, strengthen required land based construction equipment such as excavator, dump truck, chain dozer, vibro-compactor, and plants such as generator for site electrification, digital camera for taking photographs and digital video camera for recording/Taking photograph all sequences of works etc for keeping records of the Works by	LS	1.000	92026.551	Ninety- Two Thousand AND Twenty- Six point Five Five One	92026.551	Ninety- Two Thousand AND Twenty- Six point Five Five One

			information including transfer to site, complete for the purposes stated in the Technical Specification and Contractor's Method Statement and as per direction of Engineer in charge.						
6	Approved rate	Approved rate	Operate , maintain of plant and equipment such as generator for site electrification, for the purpose stated in the Technical Specification and in the Contractor's Method Statement and as per direction of Engineer in charge.	LS	1.000	110909.921	One Lakh Ten Thousand Nine Hundred and Nine point Nine Two One	110909.921	One Lakh Ten Thousand Nine Hundred and Nine point Nine Two One
7	04-150	04-150	Manufacturing and supplying R.C.C. (1:2:4) BM Pillars of size 15cmx 15cmx75cm, with 40cmx40cmx10cm base having 3 nos.10mm dia MS.bar each way at base,4nos.10mm dia vertical bar and 8nos 6mm dia ring,excluding cost of M.S.works for reinforcement but including cost of form works, concreting, plastering at top, finishing surface, curing etc. complete, with inscription of "BWDB", on exposed surface etc. complete as per direction of Engineer in charge.	nos	24.000	1500.001	One Thousand Five Hundred point Zero Zero One	36000.024	Thirty-Six Thousand point Zero Two Four
8	04-160	04-160	Fixing in position B.M. pillars and kilometer posts of size 15cmx15cmx75cm with 40cmx40cmx10cm base, embedding 45cm below G.L. including carriage, earth cutting, backfilling, ramming, etc. complete as per direction of Engineer in charge.	nos	24.000	500.001	Five Hundred point Zero Zero One	12000.024	Twelve Thousand point Zero Two Four

9	16-100	16-100	Erection of bamboo profile with full bamboo posts and pegs not less than 60mm in diameter and coir strings etc. complete as per direction of Engineer in charge.	nos	461.000	290.481	Two Hundred and Ninety point Four Eight One	133911.741	One Lakh Thirty- Three Thousand Nine Hundred and Eleven point Seven Four One
10	Approved rate	Approved rate	River dredging work as per approved design and specification including mobilizing (and subsequent demobilizing) necessary dreders, ancillary equipments, floating pipes, shore pipes and other necessary suppliies, disposal of dredged material shall not be done within river and it shall be disposed to safe distance which specified in the drawing by installing necessary floating and shore pipes with all other ancillary work complete as per requirement and direction of Engineer in charge.	cum	577753.680	164.387	One Hundred and Sixty- Four point Three Eight Seven	94975194.194	Nine Crore Forty- Nine Lakh Seventy- Five Thousand One Hundred and Ninety- Four point One Nine Four
							Grand Total:	96850586.418	Nine Crore Sixty- Eight Lakh Fifty Thousand Five Hundred and Eighty- Six point Four One Eight