ANALYSIS TEMPLATE REPORT

Primary Element		Secondary Element	Weight	Unit	Element Rate		Value
40 . Pı	rotective Work						
40-820	Constructing	double row bamboo spur : length 7.5 m to 11 m					
20.	Materials : Misc.						
	20-525	Rope : Coir String	0.0520	kg	@ Tkper Sub Total	kg	Tk
30.	Wood Work						
	30-025	Bamboo, Barrack: 7.5m long, 80-100mm dia	10.6800	No.	@ Tkper 100 : Sub Total	No.	Tk
40.	Metal Work						
	40-300	Nails, all Sizes	0.3100	kg	@ Tkper Sub Total	kg	Tk
70.	Equipment, Tools						
	70-275	Monkey staging, 227 kg: 8 hrs day	0.0328	day	@ Tkper	day	Tk
					Sub Total ———		Tk
80.	Labour						
	80-060	Boat, Engine	0.1312	day	1	day	Tk
	80-375	Labour, Unskilled	2.0330	day	*	day	Tk
					Sub Total ———		Tk
					Sum of Sub Total		Tk
					Overhead &	2.5	Tk
					Item Total		Tk
					Contractor's	10 %	Tk
					Total		Tk
					VAT	5.5 %	Tk
					Item Grand Total		Tk