## **Individual Report**

**Tender/Proposal Detail** 

Tender/Proposal

233212

Invitation Reference No. :

T-3/185, Dated: 08/10/2018.

**Closing Date and** 

Time:

Brief:

ID:

12-Nov-2018 12:10

**Opening Date and** 

Time:

12-Nov-2018 12:10

Procuring Entity: Sunamganj O&M Division-2

Re-Excavation of Piyan River from Km. 19.000 to Km. 55.575 total 36.575Km. under Dhakua haor Project in Upazilla Sunamganj Sadar & Jamalganj, Dist. Sunamganj in C/W "Haor Flood Management and Livelihood Improved Improvement Project (BWDB Part)" under Sunamganj O& M Division-2,

BWDB, Sunamganj during the FY 2018-19 & 2019-20. Package No.

(BWDB/SUNAM/HFMLIP/PW-02)

Package No	Package Description
BWDB/SUNAM/HFMLIP/PW-02.	Re-Excavation of Piyan River from Km. 19.000 to Km. 55.575 total 36.575KM under Dhakua haor in Upazilla Sunamganj Sadar & Jamalganj Dist. Sunamganj in C/W Haor Flood Management and Livelihood Improved Improvement Project BWDB Part under Sunamganj O& M Division-2 BWDB Sunamganj during the FY 2018-19 & 2019-20.

## Ataur Rahman Khan Ltd.- Ashim Singh JV (JVCA)

## **Bill of Quantities**

Bill o	Bill of Quantities								
Item	(Froun			Measurement		Unit Price	Unit Price	Total Price	Total Price
no.		Unit	Quantity	In figures (BDT)	In Words (BDT)	In Figures (BDT)	In Words (BDT)		
1	Analysis Rate	N/A	Preparetion of mobilization of the site for construction of submersoble embankment or other structural components in c/w``Haor Flood Management and Livelihood Improvement Project (BWDB part) as per Technical Specifications, including land lease, rental charges, obtaining permissions for work, developing work area, preparation of platform for temporary semi pucca site office (40sqm), CI sheet labor sheds	LS	1.000	967050.001	Nine Lakh Sixty- Seven Thousand AND Fifty point Zero Zero One	967050.001	Nine Lakh Sixty- Seven Thousand AND Fifty point Zero Zero One

			(200sqm), CI sheet stores (200 sqm), supply of wooden & cane seated furniture etc. as per specified and as per Contractor's method Statement and as per direction of Engineer in Charge.						
2	Analysis Rate	N/A	Demobilization and clean-up of the site upon completion of the works, as per Technical Specification, Contractor's Method Statement and as per direction of Engineer in Charge.	LS	1.000	112344.001	One Lakh Twelve Thousand Three Hundred and Forty- Four point Zero Zero One	112344.001	One Lakh Twelve Thousand Three Hundred and Forty- Four point Zero Zero One
3	Analysis Rate	N/A	Providing and maintaining adequate portable water supply by installing 4 nos. of tube well and sanitation facilities by installing 6 nos. of sanitary latrines for usage of labours, Officials and others for prevailing the hygenic and healthy environment at allover the working sithe as per direction of the engineer in charge.	LS	1.000	111148.001	One Lakh Eleven Thousand One Hundred and Forty- Eight point Zero Zero One	111148.001	One Lakh Eleven Thousand One Hundred and Forty- Eight point Zero Zero One
4	Analysis Rate	N/A	Mobilize, strengthen required land based construction equipment such as excavator, dump truck, chain dozer, compactor and plants such as gemetor for site electrification, digital camera for taking photographs and digital video camera for recording/Taking Photograph as sequences of works etc. for keeping records of the works by providing following information	LS	1.000	92026.001	Ninety- Two Thousand AND Twenty- Six point Zero Zero One	92026.001	Ninety- Two Thousand AND Twenty- Six point Zero Zero One

			including transfer to site, complete for the purposes stated in the technical specification and Contractor's Method Statement and as per direction of Engineer in Charge.						
5	Analysis Rate	N/A	Operate, maintain of plant and equipment such as generator for site electrification for the purpose stated in the technical specification and Contractor's Method Statement and as per direction of Engineer in Charge.	LS	1.000	110909.001	One Lakh Ten Thousand Nine Hundred and Nine point Zero Zero One	110909.001	One Lakh Ten Thousand Nine Hundred and Nine point Zero Zero One
6	Analysis Rate	N/A	Provide and maintain 1 (one) no. Engine boat with boatmen having sun and rainproof cover to facilitate supervision by the Engineer/Engineers Representative during whole construction period of the work as per Technical specification and as per direction of engineer in charge.	P/day	60.000	2497.001	Two Thousand Four Hundred and Ninety- Seven point Zero Zero One	149820.060	One Lakh Forty- Nine Thousand Eight Hundred and Twenty point Zero Six
7	NSI	N/A	Construction of Bill board at site with M.S. plates, flat bars, Tees etc of size 8'-0"x12'-0" including fabricating, machining cutting, bending, welding, forging, drilling, revetting, staging and fitting, fixing, local supply of labours including the cost of materials as specification and direction of Engineer in charge.	LS	1.000	50000.001	Fifty Thousand point Zero Zero One	50000.001	Fifty Thousand point Zero Zero One
			Part Time Employment of Environmental inspector for implementation and				Two		Two

8	NSI	N/A	reporting on environmental management plan provision for first aid box and medical assistant as per specification and direction of engineer in charge.	LS	1.000	200000.001	Lakh point Zero Zero One	200000.001	Lakh point Zero Zero One
9	04-120	04- 120	Construction of B.M. Pillars at site with first class bricks in cement mortar (1:4) of size 38cm x 38cm x 75cm on cement concrete (1:2:4) base of size 50cm x 50cm x 7.5cm with 12mm thick cement plastering (1:2) on exposed surfaces of pillar and cement morter on top (1:2), with inscription of "BWDB" with 25cm of the pillar balow ground level etc. complete including ramming the backfill and the cost of all materials as per direction of Engineer in charge.	each	74.000	1323.001	One Thousand Three Hundred and Twenty- Three point Zero Zero One	97902.074	Ninety- Seven Thousand Nine Hundred and Two point Zero Seven Four
10	16-100	16- 100	Erection of bamboo profile with full bamboo posts and pegs not less than 60mm in diameter and coir strings etc. complete as per direction of Engineer in charge.	each	3660.000	327.001	Three Hundred and Twenty- Seven point Zero Zero One	1196823.660	Eleven Lakh Ninety- Six Thousand Eight Hundred and Twenty- Three point Six Six
11	16-220	16- 220	Earth work by manual labour with clayey soil (minimum 30% clay, 0-40% silt and 0-30% sand) in construction of cross bundh/ ring bundh as per design and specification with all leads and lifts, throwing the earth in layers not exceeding 150mm in thickness, including breaking clods, rough dressing, clearing	cum	14600.000	175.001	One Hundred and Seventy- Five point Zero Zero One	2555014.600	Twenty- Five Lakh Fifty-Five Thousand AND Fourteen point Six

			the jungle, removing stumps, dug bailing and 75mm cambering etc. complete as per direction of Engineer in charge.						
12	12-310	12- 310- 20	Bailing out of water with all leads and lifts by manual labour or pump, with all arrangements for protection of ring bund and side slopes of foundation pit against erosion or washout etc. complete actual volume of work will be measured by sounding method before starting the work as per direction of Engineer in charge. by Pump	cum	41286.740	7.001	Seven point Zero Zero One	289048.467	Two Lakh Eighty- Nine Thousand AND Forty- Eight point Four Six Seven
13	16-600	16- 600	"Earth work by Mechanical Excavator ( Long Boom ) in all kinds of soil in excavation / re-excavation of channel/canal/khal etc. Including disposal of spoil-	cum	913100.000	122.001	One Hundred and Twenty- Two point Zero Zero One		Eleven Crore Thirteen Lakh Ninety- Nine Thousand One Hundred and Thirteen point One
14	16-240	16- 240	Earth work by manual labor in all kinds of soil in removing cross bundh/ ring bundh, including all leads and lifts complete and placing the spoils to a safe distance, (minimum 15m apart from the bank) as per direction of Engineer in charge	cum	11680.000	175.001	One Hundred and Seventy- Five point Zero Zero One	2044011.680	Twenty Lakh Forty- Four Thousand AND Eleven point Six Eight
									Eleven Crore Ninety- Three Lakh Seventy-

	Grand Total:	119375210.648	Five Thousand Two Hundred and Ten point Six Four Eight
--	-----------------	---------------	--

This Bill of Quantities is Electronically Signed by Mr. Md. Ataur on behalf of Ataur Rahman Khan Ltd.- Ashim Singh JV