ANALYSIS TEMPLATE REPORT

Primary Element		nt	Secondary Element	Weight	Unit	Element Rate		Value
10 . P	rotectiv	ve Work						
0-190-	-15 C	C blocks (1	:3:6): 40mm shingles;sand FM>1.5: 50cmx50c	emx50cm				
10.	Materia	ıls : Concret	<u>te</u>					
		10-040	Bricks: 1st Class	1.0000	No.	@ Tkper 1000	No.	Tk
		10-100	Cement: Portland	27.2000	kg	@ Tkper	kg	Tk
		10-380	Sand, FM >= 1.5	0.0595	cum	@ Tkper	cum	Tk
		10-505	Stone, Shingles: 40mm down graded	0.1175	cum	@ Tkper	cum	Tk
						Sub Total —		Tk
20.	Materia	ıls : Misc.						
		20-245	Diesel/ Fuel	0.1763	ltr	@ Tkper	ltr	Tk
		20-310	Lubricant (Mobile oil etc.)	0.0088	ltr	@ Tkper	ltr	Tk
		20-500	Polythene Sheet: (1.0 kg per 16.00 sqm)	0.3600	sqm	@ Tkper	sqm	Tk
		20-505	Putty	0.0020	kg	@ Tkper	kg	Tk
						Sub Total —		Tk
40.	Metal V	<u>Vork</u>						
		40-020	Angle, M.S	13.3455	kg	@ Tkper	kg	Tk (Used 60 time
								Tk (10 % Salvag
		40-020	(Angle, M.S)	0.0022	kg	@ Tkper	kg	Tk (Misc. Sundry
		40-645	Sheet, Plain G.I. 16 BWG	1.0000	sqm	@ Tkper	sqm	Tk (Used 60 time
								Tk (10 % Salvag
		40-740	Welding, Arc	160.0000	pnt	*	pnt	Tk (Used 60 time
						Sub Total ——		Tk
70.	Equipm	nent, Tools						
		70-080	Concrete Mix Machine 0.2 cum: 8 hrs day	0.0074	day	@ Tkper	day	Tk
						Sub Total ——		Tk
80.	Labour					0. 777		
		80-375	Labour, Unskilled	0.3556	day	@ Tkper	day	Tk
		80-425	Mason	0.0226	day	@ Tkper	day	Tk
		80-430	Mason, Head	0.0044	day	@ Tkper	day	Tk
		80-435	Mason, Helper	0.0110	day	@ Tkper	day	Tk
		80-500	Operator, Mixture Machine	0.0074	day	@ Tkper	day	Tk
		80-755	Welder	0.0028	day	@ Tkper	day	Tk
						Sub Total —		Tk
						Sum of Sub Total	2.5	Tk
						Overhead &	2.5	Tk
						Item Total	10.0/	Tk
						Contractor's Total	10 %	Tk
						VAT	5.5 %	Tk
						Item Grand Total	5.5 /0	Tk