ANALYSIS TEMPLATE REPORT

Primary Element		Secondary Element	Weight	Unit	Element Rate	Value	
36 . F	orm Work						
36-320	Form wor	k in floor/ roof slab with 25mm thick wooden planl	ζ.				
30.	Wood Work						
	30-02	Bamboo, Barrack: 7.5m long, 60-80mm dia	2.1333	No.	@ Tkper 100	No.	Tk (Used 8 times)
							Tk (15 % Salvage
	30-46	Wood, Seasoned & Sawn, Jam	0.0404	cum	@ Tkper	cum	Tk (Used 8 times)
							Tk (10 % Salvage
					Sub Total —		Tk
40.	Metal Work						
	40-30	Nails, all Sizes	0.1428	kg	@ Tkper	kg	Tk
	40-67	5 Sheet, Plain, G.I. 28 BWG	1.0000	sqm	@ Tkper	sqm	Tk (Used 8 times)
					Sub Total ——		Tk
80.	<u>Labour</u>						
	80-37	Labour, Skilled	0.2690	day	@ Tkper	day	Tk
	80-37	5 Labour, Unskilled	0.2690	day	@ Tkper	day	Tk
	80-42	5 Mason	0.2152	day	@ Tkper	day	Tk
	80-43) Mason, Head	0.0090	day	@ Tkper	day	Tk
					Sub Total —		Tk
					Sum of Sub Total		Tk
					Overhead &	2.5	Tk
					Item Total		Tk
					Contractor's	10 %	Tk
					Total		Tk
					VAT	5.5 %	Tk
					Item Grand Total		Tk