Tender/Proposal Detail

Tender/Proposal Invitation 233210 T-3/184, Dated: 08/10/2018. Reference No.: ID:

Closing Date and

Opening Date and 12-Nov-2018 12:00 12-Nov-2018 12:00 Time: Time:

Procuring Entity: Sunamganj O&M Division-2

> Construction of (A) Submersible embankment in between Km. 10.600 to 49.426 total 33.849 Km. (B) 7 Nos. Box Drainage Outlet (C) 9 Nos. Irrigation pipe Inlet (D) Re-excavation of 4 Nos. Khal total 7.678 km. at Different Location (E) General item of Works under Dhakua Haor Project in upazilla

Brief: Sunamganj Sadar and Jamalganj, dist. Sunamganj in c/w "Haor Flood Management and Livelihood Improvement Project (BWDB Part)" under

Sunamganj O& M Division-2, BWDB, Sunamganj during the FY 2018-19 &

2019-20. Package No. (BWDB/SUNAM/HFMLIP/PW-01)

Package No	Package Description				
BWDB/SUNAM/HFMLIP/PW- 01	Construction of A Submersible embankment in between Km. 10.600 to 49.426 total 33.849 Km. B 7 Nos. Box Drainage Outlet C 9 Nos. Irrigation pipe Inlet D Re-excavation of 4 Nos. Khal total 7.678 km at Different Location E General Work under Dhakua Haor Project in upazilla Sunamganj Sadar and Jamalganj dist. Sunamganj in c/w Haor Flood Management and Livelihood Improvement Project BWDB Part under Sunamganj O& M Division-2 BWDB Sunamganj during the FY 2018-19 & 2019-20.				

Ataur Rahman Khan Ltd.- Ashim Singh JV (JVCA)

Bill of Quantities (Re-excavation of Khal)

Bill of Quantities									
Item no.	Group	Item Code (if any)	Description of Item	Measurement Unit	Quantity	Unit Price In figures (BDT)	Unit Price In Words (BDT)	Total Price In Figures (BDT)	Total Price In Words (BDT)
			Construction of B.M. Pillars at site with first class bricks in cement mortar (1:4) of size 38cm x 38cm x 75cm on cement concrete (1:2:4) base of size 50cm x 50cm x 7.5cm with 12mm thick cement plastering (1:2)				One Thousand Three		Twenty- Two Thousand
1	04- 120	04- 120	on exposed surfaces of pillar and cement morter on top	Each	17.000	1323.001	Hundred and Twenty- Three	22491.017	Four Hundred and Ninety-

			(1:2), with inscription of "BWDB" with 25cm of the pillar balow ground level etc. complete including ramming the backfill and the cost of all materials as per direction of Engineer in charge.				point Zero Zero One		One point Zero One Seven
2	16- 100	16- 100	Erection of bamboo profile with full bamboo posts and pegs not less than 60mm in diameter and coir strings etc. complete as per direction of Engineer in charge.	each	770.000	327.001	Three Hundred and Twenty- Seven point Zero Zero One	251790.770	Two Lakh Fifty-One Thousand Seven Hundred and Ninety point Seven Seven
3	16- 220	16- 220	Earth work by manual labour with clayey soil (minimum 30% clay, 0-40% silt and 0-30% sand) in construction of cross bundh/ ring bundh as per design and specification with all leads and lifts, throwing the earth in layers not exceeding 150mm in thickness, including breaking clods, rough dressing, clearing the jungle, removing stumps, dug bailing and 75mm cambering etc. complete as per direction of Engineer in charge.	cum	3200.000	175.001	One Hundred and Seventy- Five point Zero Zero One	560003.200	Five Lakh Sixty Thousand AND Three point Two
A	12-	12-	Bailing out of water with all leads and lifts by manual labour or pump, with all arrangements for protection of ring bund and side slopes of foundation pit against erosion or	QIIM.	18037 080	7 001	Seven point	242614 702	Three Lakh Forty- Two Thousand Six

	310	20	washout etc. complete actual volume of work will be measured by sounding method before starting the work as per direction of Engineer in charge. by Pump.	CUIII	403J1.30U	<i>1</i> .UU I	Zero Zero One	J42014.130	and Fourteen point Seven Nine Eight
5	16- 600	16- 600	Earth work by Mechanical Excavator (long Boom) in all kinds of soil in excavation/ re- excavation of channel/canal/khal etc. including disposal of spoil soil up to 30m away from point of excavation with rough dressing and leveling etc. complete as per direction of Engineer- in- charge.	Cum	206690.850	122.001	One Hundred and Twenty- Two point Zero Zero One	25216490.391	Two Crore Fifty-Two Lakh Sixteen Thousand Four Hundred and Ninety point Three Nine One
6	16- 240	16- 240	Earth work by manual labor in all kinds of soil in removing cross bundh/ ring bundh, including all leads and lifts complete and placing the spoils to a safe distance, (minimum 15m apart from the bank) as per direction of Engineer in charge	cum	2560.000	175.001	One Hundred and Seventy- Five point Zero Zero One	448002.560	Four Lakh Forty- Eight Thousand AND Two point Five Six
							Grand Total:	26841392.736	Two Crore Sixty- Eight Lakh Forty- One Thousand Three Hundred and Ninety- Two point Seven Three Six

This Bill of Quantities (Re-excavation of Khal) is Electronically Signed by Mr. Md. Ataur on behalf of Ataur Rahman Khan Ltd.- Ashim Singh JV