

Individual Report

| Tender/Proposal Detail | | | |
|--------------------------------|---|-----------------------------------|----------------------|
| Tender/Proposal ID : | 233923 | Invitation Reference No. : | 464 date- 09/10/2018 |
| Closing Date and Time : | 15-Nov-2018 13:00 | Opening Date and Time : | 15-Nov-2018 13:00 |
| Procuring Entity : | Habiganj O&M Division | | |
| Brief : | Re-sectioning of Submersible embankment along the left bank of Bashira river in between km 2.420 to km 9.760 = 7.00km , Construction of New Embankment along the left bank of Bitangal khal in between km 10.00 to km 17.00=7.00km, Re-excavation of Bashira River in between km 0.000 to 20.00= 17.400km , Re-excavation of Matikata khal from km 0.000 to km 2.295 =2295.00m, Construction of 2-Vent Regulator-1 no, and Construction of 4.00m Wide Causeway -1 no in C/W "Haor Flood Management and Livelihood Improvement Project (BWDB Part)" in Upazila- Baniyachong & Ajmirigang, District- Habiganj under Habiganj O&M Division, BWDB, Habiganj during the year 2018-19& 2019-20. Package No BWDB/Hobi/HFMLIP/PW-01 | | |

| Package No | Package Description |
|------------------------|---|
| BWDB/Hobi/HFMLIP/PW-01 | Re-sectioning of Submersible embankment along the left bank of Bashira river in between km 2.420 to km 9.760 7.00km Construction of New Embankment along the left bank of Bitangal khal in between km 10.00 to km 17.007.00km Re-excavation of Bashira River in between km 0.000 to 20.00 17.400km Re-excavation of Matikata khal from km 0.000 to km 2.295 2.295km Construction of 2-Vent Regulator-1 no and Construction of 4.00m Wide Causeway -1 no under Bashira River sub-project in C/W Haor Flood Management and Livelihood Improvement Project BWDB Part in Upazila- Baniyachong & Ajmirigang District- Habiganj under Habiganj O&M Division BWDB Habiganj during the year 2018-19 & 2019-20. Package No BWDB/Hobi/ HFMLIP/PW-01 |

| NOONA-HB (JV.) (JVCA) | | | | | | | | | |
|----------------------------|--------|--------------------|---|------------------|----------|--------------------------------|-------------------------------------|---------------------------------|--------------------------------------|
| Bill of Quantities: Part A | | | | | | | | | |
| Bill of Quantities | | | | | | | | | |
| Item no. | Group | Item Code (if any) | Description of Item | Measurement Unit | Quantity | Unit Price In figures (BDT) | Unit Price In Words (BDT) | Total Price In Figures (BDT) | Total Price In Words (BDT) |
| A.1 | 04-120 | 04-120 | Construction of B.M. Pillars at site with first class bricks in cement mortar (1:4) of size 38cm x 38cm x 75cm on cement concrete (1:2:4) base of size 50cm x50cm x7.5cm with 12mm thick cement plastering (1:2) on exposed surfaces of pillar and cement | each | 14.000 | 1269.313 | One Thousand Two Hundred and Sixty- | 17770.382 | Seventeen Thousand Seven Hundred and |

| | | | | | | | | | |
|-----|--------|-----------|---|------|------------|---------|--|--------------|---|
| | 120 | 120 | mortar on top (1:2), with inscription of ? BWDB? with 25cm of the pillar below ground level etc. complete including ramming the backfill and the cost of all materials as per direction of Engineer in charge. | | | | Nine point Three One Three | | Seventy point Three Eight Two |
| A.2 | 16-100 | 16-100 | Erection of bamboo profiles with full bamboo posts and pegs not less than 16mm in dia and coir string etc. complete as per direction of Engineer in charge. | each | 140.000 | 315.075 | Three Hundred and Fifteen point Zero Seven Five | 44110.500 | Forty-Four Thousand One Hundred and Ten point Five |
| A.3 | 16-650 | 16-650-10 | Earth work by Mechanical Excavator (Long Boon) in constructing/ resectioning of embankment/canal bank/ road etc. compacted to 85%/90% maximum dry density at optimum moisture content, with reference to laboratory density test AAHSTO modified hammer, with clayey soil(minm 30% clay, 0-40% silt, 0-30% sand) within the initial lead of 30m and all lifts including throwing the spoils to profiles in layers not exceeding 230mm in thickness with clod breaking to a maximum size of 100mm, benching the side slopes, removing roots and stumps of trees of girth upto 200mm from the ground, | cum | 101648.890 | 147.324 | One Hundred and Forty-Seven point Three Two Four | 14975321.070 | One Crore Forty-Nine Lakh Seventy-Five Thousand Three Hundred and Twenty- |

| | | | | | | | | |
|----|--|--|--|--|--|--|-------------------------|---|
| | | | stripping/ploughing the base of embankment and borrow pit area, dug bailing, rough dressing including 150mm cambering at the centre of crest etc. complete, including maintenance of the same for 6 months after completion, (compaction will be done by the contractor with approved equipment, including all ancillary charges for compaction and testing) as per direction of Engineer in charge. Embankment by Mech. Equipment; ht: 0 to 4m; 85% comp. | | | | | One point Zero Seven |
| 16 | | | Earth work by carried earth (by truck/boat or any other means) supplied at contractor's own cost (including royalty) in constructing/resectioning of the embankment/ canal bank/ road etc. compacted to 85%/90% maximum dry density at optimum moisture content with reference to laboratory density test AASHTO modified hammer, with clayey soil (minimum 30% clay, 0-40% silt and 0-30% sand) beyond initial lead of 300m including throwing the spoils to profiles in layer not exceeding 230mm in thickness with clod | | | | Three Hundred and | Forty- Eight Lakh Thirty- Seven Thousand |

| | | | | | | | | | |
|-----|--------|-----------|--|-----|-----------|---------|---------------------------------|-------------|--|
| A.4 | 16-410 | 10-410-10 | breaking to maximum size of 100mm, benching the side slopes, removing roots and stumps of trees of girth upto 200mm, stripping/ploughing the base of embankment and borrow pit area, dug bailing, clearing jungles, bail out of water, rough dressing including 150mm cambering at the centre of crest with all leads and lifts complete (compaction will be done by the contractor with approved equipment including all ancillary charges for compaction and testing) as per direction of Engineer in charge. 300m to 1.00 km.(85% compaction) | cum | 12706.110 | 380.706 | and Eighty point Seven Zero Six | 4837292.314 | Thousand Two Hundred and Ninety-Two point Three One Four |
| | | | Earth work by manual labour in constructing/ resectioning of embankment/ canal bank/ road etc. compacted to 85%/90% maximum dry density at optimum moisture content, with reference to laboratory density test AAHSTO modified hammer, with clayey soil(minm 30% clay, 0-40% silt, 0-30% sand) within the initial lead of 30m and all lifts including throwing the spoils to profiles in layers not exceeding 230mm in thickness with clod breaking to a | | | | | | Twenty-Six Lakh |

| | | | | | | | | | |
|-----|--------|-----------|--|-----|------------|---------|---|-------------|---|
| A.5 | 16-120 | 16-120-10 | maximum size of 100mm, benching the side slopes, removing roots and stumps of trees of girth upto 200mm from the ground, stripping/ploughing the base of embankment and borrow pit area, dug bailing, bail out of water, rough dressing including 150mm cambering at the centre of crest etc. complete, including maintenance of the same for 6 months after completion, (compaction will be done by the contractor with approved equipment, including all ancillary charges for compaction and testing) as per direction of Engineer in charge 0 m to 3 m height with 85% compaction. | cum | 12706.110 | 205.174 | Two Hundred and Five point One Seven Four | 2606963.413 | Six Lakh Six Thousand Nine Hundred and Sixty-Three point Four One Three |
| A.6 | 16-190 | 16-190 | Extra rate for every additional lead of 15m or part thereof beyond the initial lead of 30m upto a maximum of 19 leads (30m neglected) for all kinds of earth work. (1 nos lead.) | cum | 12706.110 | 24.261 | Twenty-Four point Two Six One | 308262.935 | Three Lakh Eight Thousand Two Hundred and Sixty-Two point Nine Three Five |
| A.7 | 48-100 | 48-100 | Fine dressing & close turfing of the slope and the crest of embankment with 75mm thick, good quality durba or charkanta sods of size 200mm x 200mm, with all leads and lifts, including ramming, watering until the turf grows properly, | sqm | 175000.000 | 28.285 | Twenty-Eight point Two Eight Five | 4949875.000 | Forty-Nine Lakh Forty-Nine Thousand Eight Hundred and Seventy- |

| | | | | | | | | | |
|-----|------------|------------|---|-----|------------|--------|--------------------------------------|--------------|---|
| | | | maintaining etc. Complete (measurement will be given on well- grown grass only) as per direction of Engineer in charge. | | | | | | Five |
| A.8 | 16- 300 | 16- 300 | Royalty of specified earth taken from private land (with prior permission of the Executive Engineer on production of royalty deeds with the land owner) from the area to be selected by the contractor with mutual agreement. | cum | 114355.000 | 16.228 | Sixteen point Two Two Eight | 1855752.940 | Eighteen Lakh Fifty-Five Thousand Seven Hundred and Fifty- Two point Nine Four |
| A.9 | 48- 130 | 48- 130 | Biological protection of bare earth surface by Dholkalmi with minimum 50cm long sapling, planting @ not more than 30 cm apart including supplying, sizing, taping and nursing etc. complete as per direction of the Engineer in charge. | m | 135680.000 | 5.025 | Five point Zero Two Five | 681792.000 | Six Lakh Eighty- One Thousand Seven Hundred and Ninety- Two |
| | | | | | | | Grand Total: | 30277140.554 | Three Crore Two Lakh Seventy- Seven Thousand One Hundred and Forty point Five Five Four |

This Bill of Quantities: Part A is Electronically Signed by Mr. MD. on behalf of NOONA-HB (JV.)