## ANALYSIS TEMPLATE REPORT

Primary Element		Secondary Element	Weight	Unit	Element Rate		Value
84 . E	lectrical Worl	K					
84-300	-30 Supply & f	ix of iron clad main switch : 60 A, 500 V, TPN					
40.	Metal Work						
	40-590	Screw, 37mm	0.3333	dzn	@ Tkper	dzn	Tk
					Sub Total —		Tk
60.	Electrical Work						
	60-723	Switch, Main, 60 A, 510 V, TPN	1.0000	No.	@ Tkper	No.	Tk
					Sub Total		Tk
80.	Labour						
	80-190	Electrician	0.0415	day	@ Tkper	day	Tk
	80-200	Electrician, Helper	0.0500	day	@ Tkper	day	Tk
	80-200	(Electrician, Helper)	0.0005	day	@ Tkper	day	Tk (Misc. Sundry
					Sub Total —		Tk
					Sum of Sub Total		Tk
					Overhead &	2.5	Tk
					Item Total		Tk
					Contractor's	10 %	Tk
					Total		Tk
					VAT	5.5 %	Tk
					Item Grand Total		Tk