Brief:

**Tender/Proposal Detail** 

Tender/Proposal Invitation BWDB/HFMLIP/Kish/6313 126578

Reference No.: ,Dated: 11-10-2017 ID:

Closing Date and **Opening Date and** 

22-Nov-2017 14:30 22-Nov-2017 14:30 Time: Time:

Kishoreganj WD Division **Procuring Entity:** 

BWDB/Kish/HFMLIP/PW-17

Construction of a Submergible Embankment around Naogaon Haor Part-B in between KM 30.420 to KM 44.200 13.170 KM b Bagadia Khal Rehulator 1-Vent1.50m1.80m at KM 14.52 of Naogaon Haor Part-B c Neora Khal Rehulator 4-Vent1.50m1.80m at KM 44.230 of Naogaon Haor Part-B d 25 nos Irrigation Pipe Inlet at different chainages of Part-A & Part-B and e 5 nos Box Drainage Outlet at different chainages of Part-A and Part-B of Naogaon Haor Sub-Project in c/w Haor Flood Management and Livelihood Improvement Project BWDB Part under Kishoregange WD Division BWDB Kishoregonj during the FY2016-17 & FY2017-18.

Special Instructions:

01. Tenderers should visit the working site before submission of tender.

02. RDPP is in approval process, Notification of Award (NOA) will be issued after

approval of RDPP.

03. No claim what so ever will be entertained if NOA is not issued.

04. The work of the packages may be totally dropped, decrease or increase as per field condition/design/budget allocation for which no claim shall be entertained. 05. According to PPA 2006 Act 7(3) (Amendment) The Tenders having quoted the offer in percentage is more than 10%(ten percent) above or less than 10%(ten

percent) less of the official estimated cost will be rejected.

06. In case of credit line certificate, it should be in Letter of Commitment for Bank's under taking for Line of Credit(Form PW3-7) that attached in section -8. No alteration is allowed, in failing, tender may not be accepted. In case of Bank Statement, the amount of minimum balance shall remain constant of Tk. 275.00 Lakhs during the evaluation period. During verification, required amount of Liquid Asset if not found available in Tenderer mentioned account, then the submitted bank statement will not be considered in the evaluation. For the winner bidder, this amount

shall have to be used as a working capital for this package.

Package No	Package Description
BWDB/Kish/HFMLIP/PW- 17	Construction of a Submergible Embankment around Naogaon Haor Part-B in between KM 30.420 to KM 44.200 13.170 KM b Bagadia Khal Rehulator 1-Vent1.50m1.80m at KM 14.52 of Naogaon Haor Part-B c Neora Khal Rehulator 4-Vent1.50m1.80m at KM 44.230 of Naogaon Haor Part-B d 25 nos Irrigation Pipe Inlet at different chainages of Part-A & Part-B and e 5 nos Box Drainage Outlet at different chainages of Part-A and Part-B of Naogaon Haor Sub-Project in c/w Haor Flood Management and Livelihood Improvement Project BWDB Part under Kishoregange WD Division BWDB Kishoregonj during the FY2016-17 & FY2017-18.

## **AKA-UCL (JV)** (JVCA)

## Bill of Quantities-02 (Block Road)

Ī	Bill of Quantities										
	Item no.	Group	Item Code (if any)	Description of Item	Measurement Unit	Quantity	Unit Price In figures (BDT)	Unit Price In Words (BDT)	Total Price In Figures (BDT)	Total Price In Words (BDT)	
				Earth work in							

25	56-100	56-100	box cutting up to 1.00 m depth, in all kinds of soil with all leads, removing the spoils to a safe distance, including levelling and dressing, maintaining required cambering etc. complete, as per direction of Engineer in charge.	cum	955.500	135.038	One Hundred and Thirty- Five point Zero Three Eight	129028.809	One Lakh Twenty- Nine Thousand AND Twenty- Eight point Eight Zero Nine
26	Approved Rate	Approved Rate	BP: Preperation of bed by cutting and filling including watering to bring moisture content ±2% of OMC & compacting by appropiate mechanical means etc to attain minimum compaction 98% of MDD (standard) to obtain a minimum soaked CBR 4% etc all complete as per direction of the E-I-C.	sqm	1540.000	11.389	Eleven point Three Eight Nine	17539.060	Seventeen Thousand Five Hundred and Thirty- Nine point Zero Six
27	56-110	56-110	Construction of improved road subgrade of sand (FM>=0.8) in maximum 150mm thick layer including dressing, levelling, ramming, watering, cambering and compacting to attain minimum CBR-8% by manual labour using mallet/vibro	cum	231.000	733.054	Seven Hundred and Thirty- Three point Zero Five	169335.474	One Lakh Sixty-Nine Thousand Three Hundred and Thirty- Five point Four

			compactor including cost of all materials etc. complete as per design, drawing and direction of Engineer in charge (payment shall be made on compacted volume).				FUUI		Seven Four
28(a)	Approved Rate	Approved Rate	Manufacturing and supplying of CC blocks in leanest mix (1:2:4) in volume, with cement, sand (FM>=1.5) and stone chips (40mmdown graded), to attain a minimum 28 days cylinder strength of 15.0 N/mm2 including grading, washing shingles, mixing, laying in forms, consolidation, curing for at least 21 days, including preparation of platform, shuttering in measureable stacks etc. complete including supply of all materials ( steel shutter to be used) as per direction of Enginnner in charge. Block size: 30cm x 30cm x 30cm x 30cm	nos	17111.000	359.968	Three Hundred and Fifty- Nine point Nine Six Eight	6159412.448	Sixty-One Lakh Fifty-Nine Thousand Four Hundred and Twelve point Four Four Eight
28(b)	Approved Rate	Approved Rate	Block size: 100cm x 65cm x (10-	nos	1100.000	999.909	Nine Hundred and Ninety- Nine	1099899.900	Ten Lakh Ninety- Nine Thousand Eight Hundred

			15)cm				Nine Zero Nine		and Ninety- Nine point Nine
29	24-310- 10	24-310- 10	Flush pointing to brick works, in sand cement mortar (sand of FM>=1.3), including scaffolding, curing, raking out joints, clearing the surface etc. complete in all floors including the cost of all materials and as per direction of Engineer in charge.	sqm	1540.000	162.455	One Hundred and Sixty- Two point Four Five Five	250180.700	Two Lakh Fifty Thousand One Hundred and Eighty point Seven
30(a)	40-220	40-220- 10	Labour charge for protective works in laying CC blocks of different sizes including preparation of base, watering and ramming of base etc. complete as per direction of Engineer in charge. Within 200m	cum	275.690	1145.777	One Thousand One Hundred and Forty- Five point Seven Seven	315879.261	Three Lakh Fifteen Thousand Eight Hundred and Seventy- Nine point Two Six One
30(b)	40-220	40-220- 20	Beyond 200m	cum	275.690	2026.858	Two Thousand AND Twenty- Six point Eight Five Eight	558784.482	Five Lakh Fifty-Eight Thousand Seven Hundred and Eighty- Four point Four Eight Two
21	NGI	NICI	Environmental Monitoring through Sample Collection and analysis such as Air quality test, Surface water test, Sound Level monitoring,	1 0	1 000	240077 400	Two Lakh Forty- Nine Thousand Nine	240077 400	Two Lakh Forty-Nine Thousand Nine Hundred

31	IONI	IONI	Traffic signs and road navigation, safety provisions with first aid and medical Assistant as per direction of engineer in charge.	LO	1.000	<u>८</u> 433 <i>।</i> 1.433	and Seventy- Seven point Four Nine Nine	243311.433 343311.433	and Seventy- Seven point Four Nine Nine
							Grand Total:	8950037.633	Eighty- Nine Lakh Fifty Thousand AND Thirty- Seven point Six Three Three

This Bill of Quantities-02 (Block Road) is Electronically Signed by Mr. Md Ali on behalf of AKA-UCL (JV)