ANALYSIS TEMPLATE REPORT

Primary Element			Secondary Element	Weight	Unit	Element Rate		Value	
80 . Pl	lumbin	g Work							
80-800	Fi	tting & fixi	ng 150mm dia RCC pipe over 75mm CC a	and soling.					
10.	Materia	Materials: Concrete							
		10-040	Bricks: 1st Class	11.3400	No.	@ Tkper 1000	No.	Tk	
		10-100	Cement : Portland	0.0504	kg	@ Tkper	kg	Tk	
		10-375	Sand, FM >= 1.3	0.0055	cum	@ Tkper	cum	Tk	
						Sub Total —		Tk	
80.	Labour								
		80-375	Labour, Unskilled	0.1500	day	@ Tkper	day	Tk	
		80-375	(Labour, Unskilled)	0.0015	day	@ Tkper	day	Tk (Misc. Sundry)	
		80-560	Plumber	0.0656	day	@ Tkper	day	Tk	
		80-570	Plumber, Helper	0.0656	day	@ Tkper	day	Tk	
						Sub Total		Tk	
						Sum of Sub Total		Tk	
						Overhead &	2.5	Tk	
						Item Total		Tk	
						Contractor's	10 %	Tk	
						Total		Tk	
						VAT	5.5 %	Tk	
						Item Grand Total		Tk	