## ANALYSIS TEMPLATE REPORT

Primary Element		Secondary Element	Weight	Unit	Element Rate		Value
84 . El	ectrical Work						
84-120-	50 Concealed d	listribution wiring : light point (Jam/BRB/Sun)					
10.	Materials : Concre	<u>ete</u>					
	10-100	Cement : Portland	2.5000	kg	@ Tkper	kg	Tk
	10-380	Sand, FM >= 1.5	0.0110	cum	@ Tkper	cum	Tk
					Sub Total —		Tk
40.	Metal Work						
	40-585	Screw, 25mm	1.5000	dzn	@ Tkper	dzn	Tk
					Sub Total —		Tk
60.	Electrical Work						
	60-160	Ceiling Rose	1.0000	No.	@ Tkper	No.	Tk
	60-417	Pipe, Conduit, P.V.C., 25 mm dia	8.0000	m	@ Tkper 100	m	Tk
	60-470	Round Block	1.0000	No.	@ Tkper	No.	Tk
	60-480	Rowel Plug	1.0000	dzn	@ Tkper	dzn	Tk
	60-488	Saddles	6.0000	No.	@ Tkper	No.	Tk
	60-743	Switch, piano, 5 A	1.0000	No.	@ Tkper	No.	Tk
	60-832	Wire, Copper, SWG, No. 16	0.0800	kg	@ Tkper	kg	Tk
	60-931	Wire;PVC;1C;1.5mm <sup>2</sup> ;250/400V(BRB/JUM-	14.0000	m	@ Tkper 100	m	Tk
					Sub Total —		Tk
80.	<u>Labour</u>						
	80-190	Electrician	0.1430	day	@ Tkper	day	Tk
	80-200	Electrician, Helper	0.1430	day	@ Tkper	day	Tk
	80-200	(Electrician, Helper)	0.0014	day	@ Tkper	day	Tk (Misc. Sunda
	80-425	Mason	0.4500	day	@ Tkper	day	Tk
	80-430	Mason, Head	0.1100	day	@ Tkper	day	Tk
	80-435	Mason, Helper	0.5700	day	@ Tkper	day	Tk
		, 1	0.5700	Ž	Sub Total —		Tk
					Sum of Sub Total		Tk
					Overhead &	2.5	Tk
					Item Total		Tk
					Contractor's	10 %	Tk
					Total		Tk
					VAT	5.5 %	Tk
					<b>Item Grand Total</b>		Tk