## ANALYSIS TEMPLATE REPORT

Primar	y Element	Secondary Element	Weight	Unit	Element Rate		Value
40 . P	rotective Work	<u> </u>					
0-190-	-20 CC blocks (	1:3:6): 40mm shingles;sand FM>1.5: 50cmx50	cmx40cm				
10.	Materials : Concr	<u>ete</u>					
	10-040	Bricks: 1st Class	1.0000	No.	@ Tkper 1000	No.	Tk
	10-100	Cement : Portland	17.2000	kg	@ Tkper	kg	$Tk. \dots \dots$
	10-380	Sand, FM >= 1.5	0.0493	cum	@ Tkper	cum	Tk
	10-505	Stone, Shingles: 40mm down graded	0.0970	cum	@ Tkper	cum	Tk
					Sub Total —		Tk
20.	Materials : Misc.						
	20-245	Diesel/ Fuel	0.1410	ltr	@ Tkper	ltr	Tk
	20-310	Lubricant ( Mobile oil etc.)	0.0070	ltr	@ Tkper	ltr	Tk
	20-500	Polythene Sheet: (1.0 kg per 16.00 sqm)	0.3600	sqm	@ Tkper	sqm	Tk
	20-505	Putty	0.0020	kg	@ Tkper	kg	Tk
					Sub Total —		Tk
40.	Metal Work						
	40-020	Angle, M.S	12.2016	kg	@ Tkper	kg	Tk (Used 60 time
							Tk (10 % Salvag
	40-020	(Angle, M.S)	0.0020	kg	@ Tkper	kg	Tk (Misc. Sundr
	40-645	Sheet, Plain G.I. 16 BWG	0.8000	sqm	@ Tkper	sqm	Tk (Used 60 time
							Tk (10 % Salvag
	40-740	Welding, Arc	150.0000	pnt	•	) pnt	Tk (Used 60 time
					Sub Total —		Tk
70.	Equipment, Tools						
	70-080	Concrete Mix Machine 0.2 cum: 8 hrs day	0.0059	day	@ Tkper	day	Tk
					Sub Total —		Tk
80.	Labour				O 777		
	80-375	Labour, Unskilled	0.2849	day	@ Tkper	day	Tk
	80-425	Mason	0.0182	day	@ Tkper	day	Tk
	80-430	Mason, Head	0.0035	day	@ Tkper	day	Tk
	80-435	Mason, Helper	0.0088	day	@ Tkper	day	Tk
	80-500	Operator, Mixture Machine	0.0059	day	@ Tkper	day	Tk
	80-755	Welder	0.0022	day	@ Tkper	day	Tk
					Sub Total —		Tk
					Sum of Sub Total		Tk
					Overhead &	2.5	Tk
					Item Total	10.0/	Tk
					Contractor's Total	10 %	Tk
					VAT	55%	Tk
					Item Grand Total		Tk