

## Individual Report

### Tender/Proposal Detail

<b>Tender/Proposal ID :</b>	233924	<b>Invitation Reference No. :</b>	465 date- 09/10/2018
<b>Closing Date and Time :</b>	15-Nov-2018 13:00	<b>Opening Date and Time :</b>	15-Nov-2018 13:00
<b>Procuring Entity :</b>	Habiganj O&M Division		
<b>Brief :</b>	Re-sectioning of Sub-mersible embankment along the left bank of kushiyara river in between km 0.00 to km 26.00 length 7.23 km Construction of new retired embankment in between km0.00 to km 26.50 length 6.894km Re-excavation of Kairdhala khal from km 0.00 to km 1.6950 1.6950 km under Kairdhala ratna sub-project & Re-sectioning of Sub-mersible embankment along the right bank of khowai river from km 0.00 to km 16.020 16.020km Construction of new embankment from km 22.850 to km 31.210 8.360km Re-excavation of Satomukha khal from km 0.000 to km 1.7901.790km Re-excavation of Singair beel khal from km 0.000 to km 2.7202.720km under Aralia Khal Sub-project in C/W Haor Flood Management and Livelihood Improvement Project BWDB Part in Upazila- Ajmiriganj & Baniyachong District- Habiganj under Habiganj O&M Division BWDB Habiganj during the year 2018-19 & 2019-20 ./Package No BWDB/Hobi/HFMLIP/PW-02		

Package No	Package Description
BWDB/Hobi/HFMLIP/PW-02	Re-sectioning of Sub-mersible embankment along the left bank of kushiyara river in between km 0.00 to km 26.00 length 7.23 km Construction of new retired embankment in between km0.00 to km 26.50 length 6.894km Re-excavation of Kairdhala khal from km 0.00 to km 1.6950 1.6950 km under Kairdhala ratna sub-project & Re-sectioning of Sub-mersible embankment along the right bank of khowai river from km 0.00 to km 16.020 16.020km Construction of new embankment from km 22.850 to km 31.210 8.360km Re-excavation of Satomukha khal from km 0.000 to km 1.7901.790km Re-excavation of Singair beel khal from km 0.000 to km 2.7202.720km under Aralia Khal Sub-project in C/W Haor Flood Management and Livelihood Improvement Project BWDB Part in Upazila- Ajmiriganj & Baniyachong District- Habiganj under Habiganj O&M Division BWDB Habiganj during the year 2018-19 & 2019-20 ./Package No BWDB/Hobi/HFMLIP/PW-02

### HU-AS(JV) (JVCA)

#### Bill of Quantities: Part B

#### Bill of Quantities

Item no.	Group	Item Code (if any)	Description of Item	Measurement Unit	Quantity	Unit Price In figures (BDT)	Unit Price In Words (BDT)	Total Price In Figures (BDT)	Total Price In Words (BDT)
B.1	16-100	16-100	Erection of bamboo profiles with full bamboo posts and pegs not less than 16mm in dia and coir string etc. complete as per	each	23.000	324.821	Three Hundred and Twenty-Four point Eight	7470.883	Seven Thousand Four Hundred and Seventy point Eight

			direction of Engineer in charge.				Two One		Eight Eight Three
B.2	16-220	16-220	Earth work by manual labour with clayey soil (minimum 30% clay, 0-40% silt and 0-30% sand) in construction of cross bundh/ ring bundh as per design and specification with all leads and lifts, throwing the earth in layers not exceeding 150mm in thickness, including breaking clods, rough dressing, clearing the jungle, removing stumps, dug bailing and 75mm cambering etc. complete as per direction of Engineer in charge.	cum	8100.000	105.871	One Hundred and Five point Eight Seven One	857555.100	Eight Lakh Fifty-Seven Thousand Five Hundred and Fifty-Five point One
B.3	12-310	12-310-20	Bailing out of water with all leads and lifts by manual labour or pump, with all arrangements for protection of ring bund and side slopes of foundation pit against erosion or washout etc. complete actual volume of work will be measured by sounding method before starting the work) as per direction of Engineer in charge. By pump	cum	200000.000	1.501	One point Five Zero One	300200.000	Three Lakh Two Hundred
			Earth work by Mechanical Excavator ( Long Boom ) in all kinds of soil in excavation / re-excavation of channel/canal/khal etc. Including disposal of soil				One Hundred and		Two Crore Three Lakh Thirty

B.4	16-600	16-600	disposal of Spoil-soil by dump truck from 30m to 100m from the point of excavation with rough dressing and levelling etc. complete as per direction of Engineer-in-Charge.	cum	124772.750	162.969	Sixty-Two point Nine Six Nine	20334090.295	Twenty-Four Thousand AND Ninety point Two Nine Five
B.5	16-240	16-240	Earth work in manual labour, in all kinds of soil in removing the cross bundh/ring bundh, including all leads and lifts complete and placing the spoils to a safe distance, (minimum 15m part from the bank) as per direction of Engineer in charge.	cum	7290.000	43.869	Forty-Three point Eight Six Nine	319805.010	Three Lakh Nineteen Thousand Eight Hundred and Five point Zero One
							<b>Grand Total:</b>	21819121.288	Two Crore Eighteen Lakh Nineteen Thousand One Hundred and Twenty-One point Two Eight Eight

This Bill of Quantities: Part B is Electronically Signed by Mr. Helal on behalf of HU-AS(JV)

**Md. Anisur Rahman Chowdhury- M/s. Liberty Traders Joint Venture  
(JVCA)**

**Bill of Quantities: Part B**

Bill of Quantities

Item no.	Group	Item Code (if any)	Description of Item	Measurement Unit	Quantity	Unit Price In figures (BDT)	Unit Price In Words (BDT)	Total Price In Figures (BDT)	Total Price In Words (BDT)
			Erection of bamboo profiles				Three		Seven Thousand

B.1	16-100	16-100	with full bamboo posts and pegs not less than 16mm in dia and coir string etc. complete as per direction of Engineer in charge.	each	23.000	324.821	Hundred and Twenty-Four point Eight Two One	7470.883	Thousand Four Hundred and Seventy point Eight Eight Three
B.2	16-220	16-220	Earth work by manual labour with clayey soil (minimum 30% clay, 0-40% silt and 0-30% sand) in construction of cross bundh/ ring bundh as per design and specification with all leads and lifts, throwing the earth in layers not exceeding 150mm in thickness, including breaking clods, rough dressing, clearing the jungle, removing stumps, dug bailing and 75mm cambering etc. complete as per direction of Engineer in charge.	cum	8100.000	130.001	One Hundred and Thirty point Zero Zero One	1053008.100	Ten Lakh Fifty-Three Thousand AND Eight point One
B.3	12-310	12-310-20	Bailing out of water with all leads and lifts by manual labour or pump, with all arrangements for protection of ring bund and side slopes of foundation pit against erosion or washout etc. complete actual volume of work will be measured by sounding method before starting the work) as per direction of Engineer in charge. By pump	cum	200000.000	5.001	Five point Zero Zero One	1000200.000	Ten Lakh Two Hundred
			Earth work by Mechanical Excavator ( Long Boom ) in all						One

B.4	16-600	16-600	dumping in all kinds of soil in excavation / re-excitation of channel/canal/khal etc. Including disposal of spoil-soil by dump truck from 30m to 100m from the point of excavation with rough dressing and levelling etc. complete as per direction of Engineer-in-Charge.	cum	124772.750	120.001	One Hundred and Twenty point Zero Zero One	14972854.773	Crore Forty-Nine Lakh Seventy-Two Thousand Eight Hundred and Fifty-Four point Seven Seven Three
B.5	16-240	16-240	Earth work in manual labour, in all kinds of soil in removing the cross bundh/ring bundh, including all leads and lifts complete and placing the spoils to a safe distance, (minimum 15m part from the bank) as per direction of Engineer in charge.	cum	7290.000	130.001	One Hundred and Thirty point Zero Zero One	947707.290	Nine Lakh Forty-Seven Thousand Seven Hundred and Seven point Two Nine
							<b>Grand Total:</b>	17981241.046	One Crore Seventy-Nine Lakh Eighty-One Thousand Two Hundred and Forty-One point Zero Four Six

This Bill of Quantities: Part B is Electronically Signed by Mr. FM on behalf of Md. Anisur Rahman Chowdhury- M/s. Liberty Traders Joint Venture

NOONA-HB (JV.) (JVCA)									
Bill of Quantities: Part B									
Bill of Quantities									
						Unit	Unit		Total

Item no.	Group	Item Code (if any)	Description of Item	Measurement Unit	Quantity	Price In figures (BDT)	Price In Words (BDT)	Total Price In Figures (BDT)	Total Price In Words (BDT)
B.1	16-100	16-100	Erection of bamboo profiles with full bamboo posts and pegs not less than 16mm in dia and coir string etc. complete as per direction of Engineer in charge.	each	23.000	319.948	Three Hundred and Nineteen point Nine Four Eight	7358.804	Seven Thousand Three Hundred and Fifty-Eight point Eight Zero Four
B.2	16-220	16-220	Earth work by manual labour with clayey soil (minimum 30% clay, 0-40% silt and 0-30% sand) in construction of cross bundh/ ring bundh as per design and specification with all leads and lifts, throwing the earth in layers not exceeding 150mm in thickness, including breaking clods, rough dressing, clearing the jungle, removing stumps, dug bailing and 75mm cambering etc. complete as per direction of Engineer in charge.	cum	8100.000	165.086	One Hundred and Sixty-Five point Zero Eight Six	1337196.600	Thirteen Lakh Thirty-Seven Thousand One Hundred and Ninety-Six point Six
B.3	12-310	12-310-20	Bailing out of water with all leads and lifts by manual labour or pump, with all arrangements for protection of ring bund and side slopes of foundation pit against erosion or washout etc. complete actual volume of work will be measured by sounding method before starting the work)	cum	200000.000	6.846	Six point Eight Four Six	1369200.000	Thirteen Lakh Sixty-Nine Thousand Two Hundred

			as per direction of Engineer in charge. By pump						
B.4	16- 600	16- 600	Earth work by Mechanical Excavator ( Long Boom ) in all kinds of soil in excavation / re- excavation of channel/canal/khal etc. Including disposal of spoil- soil by dump truck from 30m to 100m from the point of excavation with rough dressing and levelling etc. complete as per direction of Engineer-in- Charge.	cum	124772.750	119.274	One Hundred and Nineteen point Two Seven Four	14882144.984	One Crore Forty- Eight Lakh Eighty- Two Thousand One Hundred and Forty- Four point Nine Eight Four
B.5	16- 240	16- 240	Earth work in manual labour, in all kinds of soil in removing the cross bundh/ring bundh, including all leads and lifts complete and placing the spoils to a safe distance, (minimum 15m part from the bank) as per direction of Engineer in charge.	cum	7290.000	165.135	One Hundred and Sixty- Five point One Three Five	1203834.150	Twelve Lakh Three Thousand Eight Hundred and Thirty- Four point One Five
							<b>Grand Total:</b>	18799734.538	One Crore Eighty- Seven Lakh Ninety- Nine Thousand Seven Hundred and Thirty- Four point Five Three Eight

This Bill of Quantities: Part B is Electronically Signed by Mr. MD. on behalf of NOONA-HB (JV.)