ANALYSIS TEMPLATE REPORT

Primar	ry Element	Secondary Element	Weight	Unit	Element Rate		Value
40 . P	rotective Work	S					
0-190-	-75 CC blocks (1:3:6): 40mm shingles;sand FM>1.5: 40cmx40c	mx15cm				
10.	Materials : Concre	<u>ete</u>					
	10-040	Bricks: 1st Class	1.0000	No.	@ Tkper 1000	No.	Tk
	10-100	Cement : Portland	5.2500	kg	@ Tkper	kg	Tk
	10-380	Sand, FM >= 1.5	0.0119	cum	@ Tkper	cum	Tk
	10-505	Stone, Shingles: 40mm down graded	0.0226	cum	@ Tkper	cum	Tk
					Sub Total —		Tk
20.	Materials : Misc.						
	20-245	Diesel/ Fuel	0.0340	ltr	@ Tkper	ltr	Tk
	20-310	Lubricant (Mobile oil etc.)	0.0017	ltr	@ Tkper	ltr	Tk
	20-500	Polythene Sheet: (1.0 kg per 16.00 sqm)	0.1875	sqm	@ Tkper	sqm	Tk
	20-505	Putty	0.0015	kg	@ Tkper	kg	Tk
					Sub Total		Tk
40.	Metal Work						
	40-020	Angle, M.S	4.8304	kg	@ Tkper	kg	Tk (Used 60 time
							Tk(10 % Salvag
	40-020	(Angle, M.S)	0.0008	kg	@ Tkper	kg	Tk (Misc. Sundry
	40-645	Sheet, Plain G.I. 16 BWG	0.2400	sqm	@ Tkper	sqm	Tk (Used 60 time
							Tk (10 % Salvag
	40-740	Welding, Arc	63.0000	pnt	•) pnt	Tk (Used 60 time
					Sub Total —		Tk
70.	Equipment, Tools						
	70-080	Concrete Mix Machine 0.2 cum: 8 hrs day	0.0014	day	@ Tkper	day	Tk
					Sub Total —		Tk
80.	<u>Labour</u>						
	80-375	Labour, Unskilled	0.0695	day	@ Tkper	day	Tk
	80-425	Mason	0.0047	day	@ Tkper	day	Tk
	80-430	Mason, Head	0.0008	day	@ Tkper	day	Tk
	80-435	Mason, Helper	0.0021	day	@ Tkper	day	Tk
	80-500	Operator, Mixture Machine	0.0014	day	@ Tkper	day	Tk
	80-755	Welder	0.0014	day	@ Tkper	day	Tk
					Sub Total —		Tk
					Sum of Sub Total		Tk
					Overhead &	2.5	Tk
					Item Total	4.0.	Tk
					Contractor's	10 %	Tk
					Total	550	Tk
					VAT Item Grand Total		Tk Tk